

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

1	Entry Vestibule	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Moisture Resistant Gypsum Wallboard or Cement Plaster	10'-0"	<ul style="list-style-type: none"> <li>▪ Moisture resistant gypsum wallboard with wall surface protection, aluminum and glass storefront system with wall surface protection, or match exterior building materials</li> <li>▪ Provide surface floor mat, recessed floor mat and frame, or foot grilles as appropriate for location of project</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
2 A 2 B	Exit Vestibule	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Moisture Resistant Gypsum Wallboard or Cement Plaster	10'-0"	<ul style="list-style-type: none"> <li>▪ Moisture resistant gypsum wallboard with wall surface protection, aluminum and glass storefront system with wall surface protection, or match exterior building materials</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
3 A 3 B	Cart Return Vestibule	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Moisture Resistant Gypsum Wallboard or Cement Plaster	10'-0"	<ul style="list-style-type: none"> <li>▪ Moisture resistant gypsum wallboard with wall surface protection, aluminum and glass storefront system with wall surface protection, or match exterior building materials</li> <li>▪ Provide surface floor mat, recessed floor mat and frame, or foot grilles as appropriate for location of project</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
4	Cashier's Office	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Gypsum Wallboard or Acoustical Panel Ceiling See Remarks	8'-0"	<ul style="list-style-type: none"> <li>▪ This is a Secure Room. Design to comply with DeCA Directive 30-18 as indicated in Chapter 1 Design Requirements</li> <li>▪ Perimeter walls and ceiling of room shall have ¾" fire retardant treated plywood beneath gypsum wallboard facing interior of this room</li> <li>▪ If perimeter walls of room extend to underside of structure above, an acoustical panel ceiling may be used. Consider overhead duct placement to avoid penetration of secure enclosure</li> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide counters and base cabinets in accordance with</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

4 Cont.							Design Standard Plate for Customer Service, Cashier's Office, and Cash Counting Room
5	Cash Counting Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room.</li> <li>▪ Provide counters and base cabinets in accordance with Design Standard Plate for Customer Service, Cashier's Office, and Cash Counting Room</li> <li>▪ Access to this room is controlled by electric door strike from Cashier's Office</li> </ul>
6 A	Customer Service	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide counters and base cabinets in accordance with Design Standard Plate for Customer Service, Cashier's Office, and Cash Counting Room</li> </ul>
6 B	Customer Service Office	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	
7	NOT USED						
8	Cart Storage	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling See Remarks	Same Height as Sales Area	<ul style="list-style-type: none"> <li>▪ Provide cart rails to identify limits of Cart Storage</li> <li>▪ Provide cart bumpers to protect wall surfaces in Cart Storage Area</li> <li>▪ Provide exposed roof structure (Painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects, unless directed otherwise by DeCA PM</li> <li>▪ Ceiling height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package, as directed by DeCA Project Manager</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
9	Family Restroom	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>
10	Customer Restroom (Men)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>
11	Customer Restroom (Women)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>
12	Store Director	Vinyl Composition	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide higher ceiling height if required to coordinate</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

12 Cont.		Tile					with exterior windows
13	Administrative Entry Vestibule	Vinyl Composition Tile	Resilient Base	See Remarks	Moisture Resistant Gypsum Wallboard or Cement Plaster	8'-0" or 10'-0"	<ul style="list-style-type: none"> <li>▪ Moisture resistant gypsum wallboard with wall surface protection, aluminum and glass storefront system with wall surface protection, or match exterior building materials</li> <li>▪ Provide surface floor mat, recessed floor mat and frame, or foot grilles as appropriate for location of project</li> </ul>
14	Administrative Corridor	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Gypsum Wallboard or Acoustical Panel Ceiling	8'-0"	
15	Administrative Area	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	10'-0"	
16A	Employee Break Room (Admin Area)	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0" or 10'-0"	<ul style="list-style-type: none"> <li>▪ Provide kitchen counter with sink (CED 4CKT) and space for refrigerator (CED 2A04), microwave (CED 2A26), and 4 seat table with chairs (CED 2A27)</li> <li>▪ Provide rigid wall covering (RWC) wainscot on all exposed wall surfaces</li> </ul>
16B	Employee Break Room (Warehouse Area)	Polished Concrete	None	CMU	Acoustical Panel Ceiling	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide kitchen counter with sink (CED 4CKT) and space for refrigerator (CED 2A04), microwave (CED 2A26), and 4 seat table with chairs (CED 2A27)</li> <li>▪ Provide rigid wall covering (RWC) wainscot on all exposed wall surfaces</li> <li>▪ Paint CMU walls</li> </ul>
17	Training Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0" or 10'-0"	<ul style="list-style-type: none"> <li>▪ Provide counter with base cabinets and open shelving, marker board, and tack boards in accordance with Design Standard Plate for Training Room Cabinets</li> <li>▪ Provide accent lighting above conference table controlled by dimmer switch</li> </ul>
18	Store Administrator	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide higher ceiling height if required to coordinate with exterior windows</li> </ul>
19	Store Manager	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide higher ceiling height if required to coordinate with exterior windows</li> </ul>
20 A	Janitor's Closet	Concrete -	Resilient	Moisture	Moisture Resistant	8'-0" min.	<ul style="list-style-type: none"> <li>▪ Provide storage shelving on adjustable wall standards</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

20 B 20 C		<b>See General Notes</b>	Base - See Remarks	Resistant Gypsum Wallboard or CMU	Gypsum Wallboard		<ul style="list-style-type: none"> <li>▪ Provide 48" high fiberglass reinforced panels (FRP) wainscot on wall surfaces above mop basin</li> <li>▪ Provide mop rack above mop basin</li> <li>▪ Resilient base not required at CMU walls</li> </ul>
21 A 21 B 21 C	Vestibule (Receiving/Staging to Sales Area)	Concrete - <b>See General Notes</b>	None	CMU / Gypsum Wallboard / Prefabricated Insulated Panel	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ CMU, gypsum wallboard, and prefabricated insulated wall panels exposed to Vestibule shall be protected with full height fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
22	Administrative Storage	Concrete - <b>See General Notes</b>	Resilient Base	Gypsum Wallboard or CMU	Gypsum Wallboard	8'-0" min.	<ul style="list-style-type: none"> <li>▪ Use CMU wall construction unless room is located in area containing all gypsum wallboard construction</li> </ul>
23	Damaged Merchandise	Concrete - <b>See General Notes</b>	None	CMU	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Paint CMU walls</li> </ul>
24	Damaged Merchandise Sales Niche	Polished Concrete or Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Gypsum Wallboard	8'-0" min.	<ul style="list-style-type: none"> <li>▪ Provide wall surface protection on all wall surfaces</li> <li>▪ Provide cased opening between rooms 23 and 24 for fixture 1R09 Damaged Merchandise Display Case</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
25	Locker Room (Women)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> <li>▪ Provide double tier metal lockers with sloped tops</li> <li>▪ Set lockers on raised concrete base. Cover exposed fronts and sides of concrete base with finish base material matching that used elsewhere in room</li> <li>▪ Provide benches for use with lockers</li> </ul>
26	Employee Restroom (Women)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>
27	Employee Restroom (Men)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>
28	Locker Room (Men)	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> <li>▪ Provide double tier metal lockers with sloped tops</li> <li>▪ Set lockers on raised concrete base. Cover exposed</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

28 Cont.							fronts and sides of concrete base with finish base material matching that used elsewhere in room <ul style="list-style-type: none"> <li>▪ Provide benches for use with lockers</li> </ul>
29	Controlled Temperature Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> </ul>
30	Contract Stocker Storage	Concrete - <b>See General Notes</b>	None	CMU or Wire Mesh Partition	Exposed Structure	10'-0" min.	
31 A	Communications Room (CISIC)	Concrete - <b>See General Notes</b>	None	Plywood	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Design room in accordance with Design Standard Plate "CISIC ROOM FLOOR PLAN" for large, medium, and small stores</li> <li>▪ Provide ¾" thick fire treated plywood on all gypsum board wall surfaces as indicated in Design Standard Plate</li> </ul>
31 B	Communications Closet (CISIC)	Concrete - See General Notes	None	Plywood	Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Design room in accordance with Design Standard Plate "CISIC SUB HUB ROOM FLOOR PLAN"</li> <li>▪ Provide ¾" thick fire treated plywood on all gypsum board wall surfaces as indicated in Design Standard Plate</li> </ul>
31 C 31 D 31 E	Mechanical Room	Concrete - <b>See General Notes</b>	Resilient Base See Remarks	Gypsum Wallboard or CMU	Moisture Resistant Gypsum Wallboard	8'-0" min. or As Required	<ul style="list-style-type: none"> <li>▪ Use CMU wall construction unless room is located in area containing all gypsum wallboard construction</li> <li>▪ Provide specific room name as appropriate (i.e., Mechanical Room, Electrical Room, Sprinkler Room, etc.)</li> <li>▪ Resilient base not required at CMU walls</li> </ul>
32	Sensitive Storage	Concrete - <b>See General Notes</b>	None	CMU or Wire Mesh Partition	Gypsum Wallboard or Exposed Construction	12'-0" min. or 17'-0" min. clear height	<ul style="list-style-type: none"> <li>▪ Ceiling not required if perimeter walls of room extend to underside of structure above</li> <li>▪ Ceiling height shall be determined based on storage racks to be located within this room.</li> </ul>
33	Operating Supply Storage	Concrete - <b>See General Notes</b>	None	CMU	Gypsum Wallboard or Exposed Construction	12'-0" min. or 17'-0" min. clear height	<ul style="list-style-type: none"> <li>▪ Ceiling not required if perimeter walls of room extend to underside of structure above</li> <li>▪ Ceiling height shall be determined based on storage racks to be located within this room.</li> </ul>
34	Medical Food Inspection Office	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard or CMU	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
35	Receiving Manager	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard or CMU	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide concrete filled bumper posts on outside exposed corners</li> </ul>
36 A	Receiving Area	Concrete - <b>See General Notes</b>	None	CMU or Concrete	Exposed Structure	17'-0" min.	<ul style="list-style-type: none"> <li>▪ A clear height of 17'-0" minimum shall be maintained from finished floor to any obstruction or structural</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

36 A Cont.		<b>Notes</b>					<ul style="list-style-type: none"> <li>▪ member</li> <li>▪ Pallet storage racks shall be bolted to floor slab with corner guard protection at each upright frame</li> <li>▪ All walls facing Receiving Area shall be full height to underside of roof structure and sealed air tight</li> <li>▪ Any gypsum wallboard or prefabricated insulated wall panels exposed to Receiving Area shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
37	Staging Area	Concrete - <b>See General Notes</b>	None	CMU or Concrete	Exposed Structure	17'-0" min.	<ul style="list-style-type: none"> <li>▪ A clear height of 17'-0" minimum shall be maintained from finished floor to any obstruction or structural member</li> <li>▪ Pallet storage racks shall be bolted to floor slab with corner guard protection at each upright frame</li> <li>▪ All walls facing Staging Area shall be full height to underside of roof structure and sealed air tight</li> <li>▪ Any gypsum wallboard or prefabricated insulated wall panels exposed to Staging Area shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
38	MHE Charging Area	Concrete - <b>See General Notes</b>	None	CMU or Concrete	Exposed Structure	17'-0" min.	<ul style="list-style-type: none"> <li>▪ A clear height of 17'-0" minimum shall be maintained from finished floor to any obstruction or structural member</li> <li>▪ Pallet storage racks shall be bolted to floor slab with corner guard protection at each upright frame</li> <li>▪ All walls facing MHE Charging Area shall be full height to underside of roof structure and sealed air tight</li> <li>▪ Any gypsum wallboard or prefabricated insulated wall panels exposed to MHE Charging Area shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
39	Mass Display Area	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling See Remarks	Same Height as Sales Area	<ul style="list-style-type: none"> <li>▪ Provide cart rails to identify limits of Mass Display Area if appropriate</li> <li>▪ Provide cart bumpers or wood bumper rails to protect wall surfaces in Mass Display Area if appropriate</li> <li>▪ Provide exposed roof structure (painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects</li> <li>▪ Ceiling height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package as directed by DeCA Project Manager</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

39 Cont.							<ul style="list-style-type: none"> <li>▪ Provide accent lighting as directed by DeCA Project Manager</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
40	NOT USED						
41	Plant Display Area	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling See Remarks	Same Height as Sales Area	<ul style="list-style-type: none"> <li>▪ Provide cart rails to identify limits of Plant Display Area if appropriate</li> <li>▪ Provide cart bumpers or wood bumper rails to protect wall surfaces in Plant Display Area if appropriate</li> <li>▪ Provide exposed roof structure (painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects</li> <li>▪ Ceiling Height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package as directed by DeCA Project Manager</li> <li>▪ Provide accent lighting as directed by DeCA Project Manager</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
42	NOT USED						
43 A	Produce Chilled Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
43 B	Produce Chilled Storage (GAS)	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

43 B Cont.							reinforced panels (FRP) and 6" high concrete curb
44 A	Produce Processing	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
44 B	Produce Ambient Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
45	Produce Manager	Vinyl Composition Tile	Resilient Base	Moisture Resistant Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide observation window into Produce Processing area</li> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide floor threshold and perimeter gasket on door frame to minimize moisture migration into office from adjacent refrigerated space</li> </ul>
46	Seafood Display Area	Resinous Flooring	Glazed Ceramic Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Slope floor to drain</li> <li>▪ Provide full height ceramic wall tile with accent pattern in accordance with the DeCA Standard Décor Package</li> <li>▪ Terminate resinous floor finish beneath display case line-up</li> </ul>
47	Meat/Produce Operating Supply Storage	Concrete - <b>See General Notes</b>	None and Concrete Curb	CMU and Prefabricated Insulated Panel	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Prefabricated insulated wall panels exposed to room shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
48	NOT USED						
49	NOT USED						
50	NOT USED						
51	Employee Restroom	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> <li>▪ See Design Criteria Division 10 "SIGNS" for required signage</li> </ul>
52	NOT USED						

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

53	Employee Restroom	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> <li>▪ See Design Criteria Division 10 "SIGNS" for required signage</li> </ul>
54	Receiving Aisle	Concrete - <b>See General Notes</b>	None	CMU or Concrete	Exposed Structure	17'-0" min.	<ul style="list-style-type: none"> <li>▪ A clear height of 17'-0" minimum shall be maintained from finished floor to any obstruction or structural member</li> <li>▪ All walls facing Receiving Aisle shall be full height to underside of roof structure and sealed air tight</li> <li>▪ Any gypsum wallboard or prefabricated insulated wall panels exposed to Receiving Aisle shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
55	Meat Processing	Resinous Flooring	Resinous Flooring on Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide red colored resinous flooring</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
56	Meat Wrapping	Resinous Flooring	Resinous Flooring on Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide red colored resinous flooring</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
57	Meat Manager	Resinous Flooring	Resilient Base	Moisture Resistant Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide observation window into Meat Processing area</li> <li>▪ Provide horizontal blinds on all windows in this room</li> <li>▪ Provide floor threshold and perimeter gasket on door frame to minimize moisture migration into office from adjacent refrigerated space</li> </ul>
58	Meat Restocking Aisle	Resinous Flooring	Resinous Flooring on Concrete Curb	Glazed Ceramic Tile	Gypsum Wallboard	8'-0" min.	<ul style="list-style-type: none"> <li>▪ Cover cold storage room insulated wall panels with gypsum wallboard on metal studs. Do not adhere gypsum wallboard directly to cold storage room insulated wall panels</li> <li>▪ Refer to Design Criteria Section "BUILDING INSULATION"</li> <li>▪ Coordinate ceiling height with DeCA standard décor package</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

59	Meat Chill Storage	Resinous Flooring	Resinous Flooring on Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide red colored resinous flooring</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
60	NOT USED						
61	Prepackaged Meat Chill Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
62	Poultry Chill Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
63	NOT USED						
64	NOT USED						
65	NOT USED						
66	NOT USED						
67	Dairy Chill Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
68	Frozen Food Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ See Division 3 "INSULATING CONCRETE FREEZER FLOORS" for required floor construction</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

69	Sales Area	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling See Remarks	18'-0" 16'-0" 14'-0" or 12'-0" See Remarks	<ul style="list-style-type: none"> <li>▪ Provide protection posts, case corner guards, and cart bumpers as appropriate for protection of display fixtures</li> <li>▪ Provide wood bumper rails to protect exposed wall surfaces in Sales Area</li> <li>▪ Provide exposed roof structure (painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects</li> <li>▪ Ceiling height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package as directed by DeCA Project Manager</li> <li>▪ Provide accent lighting as directed by DeCA Project Manager</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
70	Deli Service Area	Resinous Flooring	Glazed Ceramic Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent pattern in accordance with the DeCA Standard Décor Package</li> <li>▪ Terminate resinous floor finish beneath display case line-up</li> </ul>
71	NOT USED						
72	Bakery Service Area	Resinous Flooring	Glazed Ceramic Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent pattern in accordance with the DeCA Standard Décor Package</li> <li>▪ Terminate resinous floor finish beneath display case line-up</li> </ul>
73	Deli Preparation Area	Resinous Flooring	Glazed Ceramic Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent pattern in accordance with the DeCA Standard Décor Package</li> <li>▪ Terminate resinous floor finish beneath display case line-up</li> </ul>
74	Bakery Preparation Area	Resinous Flooring	Glazed Ceramic Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	10'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent pattern in accordance with the DeCA Standard Décor Package</li> <li>▪ Terminate resinous floor finish beneath display case line-up</li> </ul>
75	Bakery Chill Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to corridors and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

76	Bakery Freezer	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ See Division 3 "INSULATING CONCRETE FREEZER FLOORS" for required floor construction</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to staging area, receiving area, corridors, and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
77	Deli Chill Storage	Concrete - <b>See General Notes</b>	Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed to corridors and other high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
78	Bakery / Deli Dry Storage	Resinous Flooring	Resilient Base	Gypsum Wallboard	Gypsum Wallboard	10'-0"	
79	NOT USED						
80	Bagger Break Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide space for 4 seat table with chairs (CED 2A27) as determined appropriate during Design Charrette</li> <li>▪ Provide rigid wall covering (RWC) wainscot on all exposed wall surfaces</li> <li>▪ Provide double tier metal lockers with sloped tops</li> <li>▪ Set lockers on raised concrete base in rooms with permanent locker configuration.</li> <li>▪ Set lockers on built-up wood base in rooms where locker configuration could be revised</li> <li>▪ Cover exposed fronts and sides of locker bases with finish base material matching that used elsewhere in room</li> </ul>
81	Checkout	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling (See Remarks)	Same Height as Sales Area	<ul style="list-style-type: none"> <li>▪ Provide cart rails to identify limits of Checkout Area</li> <li>▪ Provide exposed roof structure (painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects</li> <li>▪ Ceiling height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package as directed by DeCA Project Manager</li> <li>▪ Provide accent lighting as directed by DeCA Project Manager</li> <li>▪ Provide wood bumper rails to protect exposed wall surfaces</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

81 Cont.							<ul style="list-style-type: none"> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
82	Customer Checkout Queuing	Polished Concrete or Vinyl Composition Tile	Resilient Base	See Remarks	Exposed Structure or Acoustical Panel Ceiling See Remarks	Same Height as Sales Area	<ul style="list-style-type: none"> <li>▪ Provide protection posts with bumpers are jambs of customer exit doors and carry-out return doors</li> <li>▪ Provide cart bumpers as appropriate to protect storefront systems</li> <li>▪ Provide wood bumper rails to protect exposed wall surfaces</li> <li>▪ Provide exposed roof structure (painted) on new construction projects</li> <li>▪ Provide acoustical panel ceiling on addition/alteration projects</li> <li>▪ Ceiling height shall be as determined during Design Charrette, using DeCA standard 18'-0", 16'-0", 14'-0", or 12'-0" Standard Décor Package as directed by DeCA Project Manager</li> <li>▪ Provide accent lighting as directed by DeCA Project Manager</li> <li>▪ Provide polished concrete floor finish on new construction projects</li> <li>▪ Provide vinyl composition tile (VCT) floor finish on addition/alteration projects or match existing if only partial replacement is required</li> </ul>
83	Mechanical Mezzanine	Concrete	None and Resilient Base	CMU and Moisture Resistant Gypsum Wallboard	Exposed Structure	8'-0" min. or As Required	<ul style="list-style-type: none"> <li>▪ Provide resilient base on gypsum wallboard partitions</li> <li>▪ Provide sound attenuation blankets within gypsum wallboard partitions to minimize sound transmission</li> <li>▪ Seal penetrations in floors, walls, and ceilings to minimize sound transmission</li> </ul>
84	Vendors Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide 24" deep x 30" high work counter</li> </ul>
85	Seafood Chill Storage	Resinous Flooring	Resinous Flooring on Concrete Curb	Prefabricated Insulated Panel	Prefabricated Insulated Panel	10'-0"	<ul style="list-style-type: none"> <li>▪ Refrigerated cold storage room</li> <li>▪ Slope floor to drain</li> <li>▪ Provide red colored resinous flooring</li> <li>▪ Provide concrete curb on all exposed wall surfaces</li> <li>▪ Prefabricated insulated wall panels exposed high traffic areas shall be protected with 8'-0" high fiberglass reinforced panels (FRP) and 6" high concrete curb</li> </ul>
86	Bagger Restroom	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> </ul>

**DeCA DESIGN CRITERIA HANDBOOK  
STANDARD COMMISSARY ROOM AND FINISH SCHEDULE**

86 Cont.							<ul style="list-style-type: none"> <li>▪ See Design Criteria Division 10 "SIGNS" for required signage</li> </ul>
87	Perishable Manager	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
88	Semi-Perishable Manager	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
89	Zone Manager	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
90	Region Management Support Office	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
91	Region Management Support Storage	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	
92	Conference Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide horizontal blinds on all windows in this room</li> </ul>
93	Cashier Locker / Break Room	Vinyl Composition Tile	Resilient Base	Gypsum Wallboard	Acoustical Panel Ceiling	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide space for 4 seat table with chairs (CED 2A27) as determined appropriate during Design Charrette</li> <li>▪ Provide rigid wall covering (RWC) wainscot on all exposed wall surfaces</li> <li>▪ Provide double tier metal lockers with sloped tops</li> <li>▪ Set lockers on raised concrete base in rooms with permanent locker configuration.</li> <li>▪ Set lockers on built-up wood base in rooms where locker configuration could be revised</li> <li>▪ Cover exposed fronts and sides of locker bases with finish base material matching that used elsewhere in room</li> </ul>
94	Cashier Restroom	Unpolished Paver Tile	Unpolished Paver Tile	Glazed Ceramic Tile	Moisture Resistant Gypsum Wallboard	8'-0"	<ul style="list-style-type: none"> <li>▪ Provide full height ceramic wall tile with accent band or pattern</li> <li>▪ See Design Criteria Division 10 "SIGNS" for required signage</li> </ul>

**GENERAL NOTES**

- (1) Room numbers indicated in Schedule are typical for a commissary facility. All room types listed may or may not be required on a particular project. During development of the concept floor plan, the need for each room type should be addressed for applicability. Provide documentation in project file of reason that any room type is not required on project.
- (2) See "General Design Information" for additional guidance relating to materials and finishes on new construction projects and addition/alteration projects.
- (3) Exposed concrete floors in building (other than polished concrete finish in customer areas) shall have 2 coats of acrylic liquid floor sealing treatment, applied in accordance with Division 3 "CAST-IN-PLACE CONCRETE". **Clarify this construction requirement on Room Finish Schedule.**
- (4) Do not paint exposed CMU walls in non-customer areas, except in occupied office areas. On addition / alteration projects, paint all existing and new CMU to match.
- (5) All exposed gypsum wallboard shall be finish painted. Non-exposed gypsum wallboard shall be taped, sanded, and primed. Gypsum wallboard behind display cases shall be finish painted.
- (6) Do not paint exposed roof structure (including utilities) in non-customer areas. Paint exposed roof structure (including utilities) in customer areas. A/E NOTE: Confirm that metal primer specified is compatible with finish coat applied on metal surfaces to be painted.